

Estimated Bill of Quantity (Civil)					
No.	Description	Unit	Quantity	Unit Price \$	Total price \$
1	Architecture				
1.1	Site preparation demolishing works complete with cleaning at completion of the works and removal of waste	LS	1		0
1.2	Back filling with adasia to form new 4 steps complete with tiles at new entrance	LS	1		0
1.3	Steel work for covering northern facade	kg	2200		0
1.4	Modifying existing steel frame where it contradicts new walls	LS	1		0
1.5	supplying and installing sandwich panel wall same as existing	m2	40		0
1.6	dismantling and reinstalling sandwich panels at new location according to drawings	m2	20		0
1.7	Supplying and installing Gypsum board walls, ceiling and partitions	m2	250		0
1.8	Supplying and installing styrofoam thermal isolation for Gypsum board walls and ceiling	m2	100		0
1.9	Repairing and polishing existing tiles	m2	80		0
1.10	Painting works for all walls and ceiling	m2	250		0
1.11	Supplying and installing Wooden doors complete with all accessories and painting	Nos	2		0
1.12	Check and repair when necessary the existing rain drain system on the existing two roofs by changing down spot pipes to 4" pipes and making new side drains	LS	1		0
1.13	Supplying and installing steel pedestrian door	Nos	2		0
2	Water Tanks Platform				
2.1	supplying and installing steel platform for water tanks according to drawings	kg	2000		0
2.2	Relocating water tanks at steel platform including water and electrical connections	LS	1		0
3	Aluminum Windows				
3.1	Supplying and installing marble frames for aluminum windows at northern façade	mr	12		0
3.2	Supplying and installing aluminum windows	m2	15		0
3.3	Supplying and installing frame catchers foraluminum windows	mr	42		0
3.4	Supplying and installing SRF (Shutter Resistant Film) minimum 7mil for aluminum windows	m2	15		0
4	Emergency Escape Stairs				
4.1	Excavation for emergency escape steel stairs foundation	m3	5		0
4.2	Blind concrete for emergency escape steel stairs foundation	m3	1		0

	4.3	Reinforced concrete for emergency escape steel stairs foundation	m3	4		0
	4.4	Steel work for emergency escape stairs	kg	3000		0
	4.5	Painting emergency escape steel stairs	LS	1		0
Subtotal						0

Estimated Bill of Quantity (Electrical)						
No.	Item	Description	Unit	Quantity	Unit Price \$	Total Price \$
2	Lighting					
	2.1	supply and install lighting LED hidden lights with 25W ,LED spotlights including wiring PVC conduits from electrical panel to switch and from switch to light point ,surface box and all accessories required.	No	40		0
3	Sockets					
	3.1	supply and install socket including wiring PVC conduits from electrical panel to socket with choko socket 16 A , with white cover plate and steel chassis and all accessories required.	No	8		0
4	Fire Alarm System					
	4.2	Smock detector: supply and install smock detector with base including fire alarm cable to fire panel	No	7		0
	4.3	Heat detector: supply and install heat detector with base including fire alarm cable to fire panel	No	1		0
5	CCTV System					
	5.1	Relocating of existing cameras	No	2		0
6	Data					
	6.1	Supply and install Data and voice socket including testing and commissioning with all required installations including cables, outlets covers....etc.	No	16		0
	6.2	Supply and install 24 Port Cat-6 Patch Panel UTR RJ-45	No	3		0
Subtotal						0

No.	Description	Unit	Quantity	Unit Price	Total Price	
1	Air Conditioning					
	1.1	Supply and install Air Conditioner 12000 BTU/h, and all required electrical installation, fittings and copper	No	1	0	
	1.2	Supply and install Air Conditioner 18000 BTU/h, and all required electrical installation, fittings and copper	No	1	0	
	1.3	Relocating existing out door A/C units	No	2	0	
3	Fire Extinguishers					
	3.2	Supply and install automatic 6 kg CO2 Fire Extinguishers for stores	No	2	0	
Subtotal						0
Total for civil, electrical and mechanical works:					0	

Signature and stamp of the Bidder:	
Name:	
Title:	
Name of Company:	
Telephone:	
Email:	